



NOTES:

1. DRIVEWAY TO BE PORTLAND CEMENT CONCRETE, MIN. 3000 P.S.I. @ 28 DAYS.
2. BASE TO BE A MINIMUM 4 INCHES OF CLEAN SAND OR SANDY LOAM, FULLY COMPACTED, FULL WIDTH.
3. CONCRETE TO BE BROOM FINISHED WITH EVEN, DUSTLESS SURFACE.

FILEPATH: P:/DGN/ENG SER/LAND DEVELOPMENT STANDARDS/DWF FORMAT/300.1C

PALM BEACH COUNTY DEPARTMENT OF ENGINEERING & PUBLIC WORKS				RESIDENTIAL DRIVEWAY CURB & GUTTER SECTION (CONCRETE)		TABLE
DRAWN BY:	DATE:	REVISED BY:	DATE:	APPROVED:		300.1C
K.L.	05/23/90	J.M.K.	02/01/2018	EFFECTIVE:		
				COUNTY ENGINEER OR DESIGNEE		